AMBRUS COMPANY LLC
2601 KUTZTOWN RD.
READING, PA 19605 US
610-921-2144
stevejr@ambruscompanyllc.com
www.ambruscompanyllc.com

Estimate

ADDRESS
Maidencreek Township
1 Quarry Rd,
Blandon, PA 19510

ESTIMATE # 1109
DATE 03/19/2021

JOB NAME
Catch Basin Repair

DESCRIPTION	QTY	RATE	AMOUNT
Project location: Sycamore Ln and Hill Rd			
EXCAVATION: -PA One Call -Mobilization -Remove/ Replace existing C-tops and riser. (Reuse existing grate) -Install new fast set morter mix around all penetrations in box -Install new 2A modified stone around catchbasin (Compacted) -Install topsoil, seed, and straw on lawn side -Repair blacktop with 5" 25mm, and 1.5" 9.5mm -Hot tar all joints	2	3,100.00	6,200.00
CONCRETE CURB: - Remove and Replace existing 18" concrete curb as agreed. -Topsoil seed and straw lawn side -Install 5" 25mm and 1.5" 9.5mm	1	1,200.00	1,200.00
Notes: Permits/ Testing by others All Safety traffic devices/ barricades supplied and maintained by Ambrus Company LLC. All concrete to be 4000psi ae			

TOTAL **$7,400.00**

Accepted By

Accepted Date

HIC# PA04139

A service charge of 18% per year will be added if not paid within terms. If not paid within terms, and legal action is taken, customer agrees to pay all costs resulting from legal fees.